Guidance on power station closure, decommissioning and handover for demolition or sale





GUIDANCE ON POWER STATION CLOSURE, DECOMMISSIONING AND HANDOVER FOR DEMOLITION OR SALE

First edition

May 2020

Published by **Energy Institute, London**

The Energy Institute is a professional membership body incorporated by Royal Charter 2003 Registered charity number 1097899 The Energy Institute (EI) is the chartered professional membership body for the energy industry, supporting over 23 000 individuals working in or studying energy and 200 energy companies worldwide. The EI provides learning and networking opportunities to support professional development, as well as professional recognition and technical and scientific knowledge resources on energy in all its forms and applications.

The El's purpose is to develop and disseminate knowledge, skills and good practice towards a safe, secure and sustainable energy system. In fulfilling this mission, the El addresses the depth and breadth of the energy sector, from fuels and fuels distribution to health and safety, sustainability and the environment. It also informs policy by providing a platform for debate and scientifically-sound information on energy issues.

The EI is licensed by:

- the Engineering Council to award Chartered, Incorporated and Engineering Technician status, and
- the Society for the Environment to award Chartered Environmentalist status.

It also offers its own Chartered Energy Engineer, Chartered Petroleum Engineer, and Chartered Energy Manager titles.

A registered charity, the El serves society with independence, professionalism and a wealth of expertise in all energy matters.

This publication has been produced as a result of work carried out within the Technical Team of the EI, funded by the EI's Technical Partners. The EI's Technical Work Programme provides industry with cost-effective, value-adding knowledge on key current and future issues affecting those operating in the energy sector, both in the UK and internationally.

For further information, please visit http://www.energyinst.org

The El gratefully acknowledges the financial contributions towards the scientific and technical programme from the following companies:

ADNOC

BP Exploration Operating Co Ltd

BP Oil UK Ltd

Chevron North Sea Ltd

Chevron Products Company

Chrysaor

Phillips 66

Qatar Petroleum

Repsol Sinopec

RWE npower

Saudi Aramco

Scottish Power

CLH SGS

ConocoPhillips Ltd Shell UK Oil Products Limited

DCC Energy Shell U.K. Exploration and Production Ltd

Drax Group Siemens Gamesa Renewables

EDF Energy Spirit Energy EDPR SSE

ENI TAOA Bratani E. ON UK Total E&P UK Limited Total UK Limited Equinor ExxonMobil International Ltd Tullow Oil Innogy Uniper Ithaca Energy Valero Intertek Vattenfall Kuwait Petroleum International Ltd Vitol Energy Nexen CNOOC Woodside Neptune Energy World Fuel Services

Ørsted

However, it should be noted that the above organisations have not all been directly involved in the development of this publication, nor do they necessarily endorse its content.

Copyright © 2020 by the Energy Institute, London.

The Energy Institute is a professional membership body incorporated by Royal Charter 2003.

Registered charity number 1097899, England

All rights reserved

No part of this book may be reproduced by any means, or transmitted or translated into a machine language without the written permission of the publisher.

ISBN 978 1 78725 193 9

Published by the Energy Institute

The information contained in this publication is provided for general information purposes only. Whilst the Energy Institute and the contributors have applied reasonable care in developing this publication, no representations or warranties, express or implied, are made by the Energy Institute or any of the contributors concerning the applicability, suitability, accuracy or completeness of the information contained herein and the Energy Institute and the contributors accept no responsibility whatsoever for the use of this information. Neither the Energy Institute nor any of the contributors shall be liable in any way for any liability, loss, cost or damage incurred as a result of the receipt or use of the information contained herein.

Hard copy and electronic access to EI and IP publications is available via our website, **https://publishing.energyinst.org**. Documents can be purchased online as downloadable pdfs or on an annual subscription for single users and companies. For more information, contact the EI Publications Team.

CONTENTS

				Page
Fore	word .			7
Ackn	owled	lgements	·	8
_				
1	Intro	duction		9
2	Over	view		12
3	Onei	rational r	phase	13
_	3.1		funding	
	5	3.1.1	Specific decommissioning fund	
		3.1.2	Provision carrying strategy	
		3.1.3	Decommissioning cost/liability estimates	
	3.2		perational lifetime projections	
	0.2	3.2.1	Factors that may affect plant lifetime	
	3.3		or demolition as part of plant modifications	
	3.4		on of information	
4	Dlani	nina nha	se	10
4	4.1		governance and management	
	4.1	4.1.1	Project definition	
		4.1.1		
		4.1.2	Project development	
		4.1.3	Project refinement	24
		4.1.4	demolition and remediation	26
		4.1.5	Project closeout	
	4.2			
	4.2		development plan/project execution plan	
	4.5	4.3.1		
		4.3.1	Existing company staff	
		4.3.2	· ·	
		4.3.4	Specialist contractors	
	4.4		Specialist advisors	
	4.4 4.5		9	
	4.5		ion of CDM regulations	
	4.6		Responsibilities under CDM regulations	
	4.0	4.6.1	dentification and recording	
		4.6.1		
		4.6.2	Risk reduction	
		4.6.4	Risk quantification	
	17		HAZMAT survey	
	4.7	4.7.1	Asbestos and hazardous insulation materials (HIM)	
		4.7.1		
		4.7.2 4.7.3	Structural surveys	
		4.7.3 4.7.4	j ,	
		4.7.4 4.7.5	Ecological survey	
		4.7.0	1101010101000000000000000000000000000	44

Contents continued

4.7.6 Invasive weed survey 4.7.7 Unexploded ordnance (UXO) preliminary risk assessment 4.7.8 Soil and groundwater investigations 4.7.9 Drainage survey 4.8 Planning regulations and permission 4.9 Decommissioning philosophy/design 4.10 Site security 4.11 Project risk register/assessment 4.12 Pre-construction information pack (PCIP) and specification/scope of works (SoW) 4.12.1 Pre-construction information pack (PCIP) 4.12.2 Scope of works (SoW) 4.13 Commercial strategy 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification 4.14.3 Tender design 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan 4.15.1 Satisfactory state 4.16 Associated legislation and guidance 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1 Isolation strategies 6.2.1 Decontamination 6.2.2 Bulk removal 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3.1 Construction phase plan 7.3.2 Traffic management plan					Page
4.7.8 Soil and groundwater investigations. 4.7.9 Drainage survey. 4.8 Planning regulations and permission 4.9 Decommissioning philosophy/design 4.10 Site security. 4.11 Project risk register/assessment 4.12 Pre-construction information pack (PCIP) and specification/scope of works (SoW). 4.12.1 Pre-construction information pack (PCIP) 4.13 Commercial strategy. 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification 4.14.3 Tender design. 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works. 6.5 Cient documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan			476	Invasive weed survey	45
4.7.8 Soil and groundwater investigations. 4.7.9 Drainage survey. 4.8 Planning regulations and permission 4.9 Decommissioning philosophy/design 4.10 Site security. 4.11 Project risk register/assessment 4.12 Pre-construction information pack (PCIP) and specification/scope of works (SoW) 4.12.1 Pre-construction information pack (PCIP) 4.12.2 Scope of works (SoW) 4.13 Commercial strategy 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification 4.14.3 Tender design. 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan. 4.15 Environmental permit closure plan. 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.7 C					
4.7.9 Drainage survey 4.8 Planning regulations and permission 4.9 Decommissioning philosophy/design 4.10 Site security. 4.11 Project risk register/assessment 4.12 Pre-construction information pack (PCIP) and specification/scope of works (SoW). 4.12.1 Pre-construction information pack (PCIP) 4.12.2 Scope of works (SoW) 4.13 Commercial strategy 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification. 4.14.3 Tender design. 4.14.4 Bonds 4.14.5 Tender 4.15 Enwironmental permit closure plan. 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination 6.2.1 Decontamination 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3.1 Construction phase plan					
4.8 Planning regulations and permission 4.9 Decommissioning philosophy/design 4.10 Site security. 4.11 Project risk register/assessment 4.12 Pre-construction information pack (PCIP) and specification/scope of works (SoW) 4.12.1 Pre-construction information pack (PCIP) 4.12.2 Scope of works (SoW) 4.14.1 Commercial strategy 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification 4.14.3 Tender design. 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan. 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2.1 Decontamination 6.2.1 Decontamination 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3.1 Construction phase plan					
4.9 Decommissioning philosophy/design 4.10 Site security. 4.11 Project risk register/assessment 4.12 Pre-construction information pack (PCIP) and specification/scope of works (SoW) 4.12.1 Pre-construction information pack (PCIP) 4.12.2 Scope of works (SoW) 4.13 Commercial strategy 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification 4.14.3 Tender design. 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan. 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3.1 Construction phase plan		4.8			
4.10 Site security. 4.11 Project risk register/assessment 4.12 Pre-construction information pack (PCIP) and specification/scope of works (SoW). 4.12.1 Pre-construction information pack (PCIP). 4.12.2 Scope of works (SoW) 4.13 Commercial strategy. 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification. 4.14.3 Tender design. 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan. 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale 7.1 Overview. 7.2 Client documentation 7.3.1 Construction phase plan					
4.11 Project risk register/assessment 4.12 Pre-construction information pack (PCIP) and specification/scope of works (SoW) 4.12.1 Pre-construction information pack (PCIP) 4.12.2 Scope of works (SoW) 4.13 Commercial strategy 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification 4.14.3 Tender design 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan					
4.12 Pre-construction information pack (PCIP) and specification/scope of works (SoW) 4.12.1 Pre-construction information pack (PCIP) 4.12.2 Scope of works (SoW) 4.13 Commercial strategy 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification. 4.14.3 Tender design. 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan. 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation. 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination. 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3 Principal construction phase plan					
specification/scope of works (SoW) 4.12.1 Pre-construction information pack (PCIP) 4.12.2 Scope of works (SoW) 4.13 Commercial strategy 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification 4.14.3 Tender design. 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan. 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination 6.2.1 Decontamination 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale 7.1 Overview. 7.2 Client documentation 7.3.1 Construction phase plan					15
4.12.1 Pre-construction information pack (PCIP) 4.12.2 Scope of works (SoW) 4.13 Commercial strategy 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification 4.14.3 Ender design 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination 6.2.1 Decontamination 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3.1 Construction phase plan		1.12			50
4.12.2 Scope of works (SoW) 4.13 Commercial strategy. 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification. 4.14.3 Tender design. 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan. 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works. 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale 7.1 Overview. 7.2 Client documentation 7.3.1 Construction phase plan			•		
4.13 Commercial strategy 4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification 4.14.3 Tender design 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan. 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale 7.1 Overview. 7.2 Client documentation 7.3.1 Construction phase plan					
4.14 Contractor selection 4.14.1 Contractor long list 4.14.2 Pre-qualification 4.14.3 Tender design 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan. 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan		<i>/</i> 113			
4.14.1 Contractor long list 4.14.2 Pre-qualification 4.14.3 Tender design 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale. 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan					
4.14.2 Pre-qualification 4.14.3 Tender design 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3 Principal contractor documentation 7.3 Principal contractor documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan		4.14			
4.14.3 Tender design. 4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan. 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan					
4.14.4 Bonds 4.14.5 Tender 4.15 Environmental permit closure plan 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan					
4.14.5 Tender 4.15 Environmental permit closure plan. 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan					
4.15 Environmental permit closure plan 4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works. 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan					
4.15.1 Satisfactory state 4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works. 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan		<i>1</i> 1 F			
4.16 Associated legislation and guidance. 5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan		4.15			
5 Late life operation 5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan		116			
5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3.1 Construction phase plan		4.10	Associat	ed legislation and guidance	60
5.1 Supply agreements 5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3.1 Construction phase plan	_				
5.2 Maintenance regime 5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan	5				
5.3 Personnel issues. 5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3.1 Construction phase plan					
5.4 Other stakeholders 6 Decommissioning phase 6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan				3	
6 Decommissioning phase 6.1 Isolation strategies. 6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works. 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan					
6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan		5.4	Other st	akeholders	63
6.1 Isolation strategies 6.1.1 Physical disconnection 6.2 Decontamination 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan	_	Dane		ulu u uhasa	CA
6.1.1 Physical disconnection 6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan	6				
6.2 Decontamination. 6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan		6.1			
6.2.1 Decontamination strategies 6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan		<i>c</i> 2			
6.2.2 Bulk removal 6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan		6.2			
6.2.3 Cleaning 6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan					
6.2.4 Draining of low points 6.3 Plant preparation 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan					
6.3 Plant preparation. 6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan					
6.4 Quality assurance 6.5 Control of works 6.5.1 Permit to work (PTW) 7 Handover for demolition or sale 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan		6.0			
6.5 Control of works . 6.5.1 Permit to work (PTW). 7 Handover for demolition or sale . 7.1 Overview . 7.2 Client documentation . 7.3 Principal contractor documentation . 7.3.1 Construction phase plan					
7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan					
7 Handover for demolition or sale. 7.1 Overview. 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan		6.5			
 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan 			6.5.1	Permit to work (PTW)	71
 7.1 Overview 7.2 Client documentation 7.3 Principal contractor documentation 7.3.1 Construction phase plan 	7	Hen.	dovor for	domolition or sale	72
7.2 Client documentation	/				
7.3 Principal contractor documentation					
7.3.1 Construction phase plan					
·		1.3			
7.3.2 Irattic management plan				· · · ·	
			1.3.2	iranic management plan	/6

Contents continued Page 7.3.3 7.3.4 7.4 **Annexes** Annex A Annex B Annex C C.1 Annex D D.1 Introduction D.2 D.3 **D.4** D.5 D.6 Inflation of demolition costs......87 D.7 **D.8** D.9 Annex E Sale of plant and equipment.....90 Annex F Annex G G.1 G.1.1 G.1.2 G.1.3 G.2 G.3 Implementation of remediation strategy......94 G.4 G.5 Annex H Glossary of terms, abbreviations and acronyms96 Terms.......96 H.1 H.2 Annex I References.......99 I 1 1.2

LIST OF FIGURES AND TABLES

Figure		Page
Figure 1	Example risk matrix, combining risk consequence on one axis, and risk probability on another (note, it is for the organisation to determine the risk categories (colour placement))	39
Tables		
Table 1 Table 2 Table 3	Example of risk consequences	38

FOREWORD

A number of (primarily) coal-fired power stations are expected to be decommissioned in the United Kingdom (UK) in the next 5–10 years. Upon handing over a power station to a specialist contractor for demolition, it is important that the power station is 'cold and dark' – i.e. hazards are isolated, the facility is decontaminated – and that all required information about the status of the plant (remaining hazards, etc.) are provided to the contractor.

This publication provides guidance on a typical project process to safely and economically prepare a power station for decommissioning and for its handover in a safe state for demolition. The guidance has been developed based on the experience of operators and references other guidance where appropriate.

The guidance covers the entire decommissioning life cycle, including preparation for the end of life during the plant operational lifetime, the late-life operations phase and into the actual decommissioning phase itself. General guidance on certain aspects of the demolition phase is also included to aid in planning, although this phase itself is beyond the scope of this publication.

The guidance does not provide the engineering detail required to safely carry out decommissioning or demolition. It instead focuses on planning, information gathering, contractor selection, general processes, and legislative requirements. Furthermore, whilst this publication covers some aspects of demolition, it only does so to make owner/operating companies aware of their responsibilities, and where this information is beneficial for planning prior to decommissioning.

This publication is primarily intended for station owners, station operators, decommissioning engineers, demolition engineers and project managers.

It should be noted this publication is guidance only; it is not a manual. Every power station is different, and each will have its own unique issues to manage.

The information contained in this document is provided for general information purposes only. Whilst the Energy Institute (EI) and the contributors have applied reasonable care in developing this publication, no representations or warranties, expressed or implied, are made by the EI or any of the contributors concerning the applicability, suitability, accuracy or completeness of the information contained herein and the EI and the contributors accept no responsibility whatsoever for the use of this information. Neither the EI nor any of the contributors shall be liable in any way for any liability, loss, cost or damage incurred as a result of the receipt or use of the information contained herein.

The EI welcomes feedback on its publications. Feedback or suggested revisions should be submitted to:

Technical Department
Energy Institute
61 New Cavendish Street
London, W1G 7AR
e: technical@energyinst.org